

SHIVAJI COLLEGE, UNIVERSITY OF DELHI
RAJA GARDEN, RING ROAD
NEW DELHI -110027

Date :- 21/06/2017

Corrigendum for Civil works Contract

TECHNICAL SPECIFICATIONS

Specifications for Flooring, Varnish and Construction of Stage

Flooring

Area (Appox.)= 5000 sq ft.

1. Flooring: Breaking the old partially broken floor in the rooms and the corridor and removing the debris.
2. Construction of Cement Concrete floor - 2 inch thick layer of cement concrete with mixing ratio of 1:2:4.
3. Finishing the floor with a 2 mm thick layer of cement.

Varnish

Area (Appox.)= 8000 sq ft.

Cleaning the surface of dust and applying two or more coats of varnish.

Stage

Area (Appox.)= 20 x 30 x 3

1. Foundation with a depth of 1 foot below ground with PCC (50mm).
2. Brickwork -230 mm to a height of 3 feet above ground; filling the internal space by compacting material, covered by a 3 inch thick cement concrete with mixing ratio of 1:2:4 and finishing with a 2 mm thick layer of cement. Outer plaster (Ratio 1:4) of brickwork. Construction of stairs on one side and a 4 ft wide ramp on the other side.


Principal